

# Possible Collaboration with the Energy Frontier Group

- The group currently
  - has 6 members
  - was funded by the Muon Accelerator Program studying Muon Colliders and Neutrino Factories
  - but this is now coming to an end
  - and we are looking for new projects
- We have expertise in:
  - Superconducting and pulsed magnets
  - Energy deposition studies
  - Radiation Damage Studies
  - Beam dynamics

# Some accelerator issues for a 100 TeV pp collider

R.Palmer, J.S. Berg, R.Gupta, D.Stratakis, H.Witte  
(BNL)

Y. Alexahin (FNAL)

V. Litvinenko (SUNY)

These ideas have been developed in discussions with FCC and others and have, in earlier form, been reported to the HEPAP Accelerator R&D Panel

1. Luminosity considerations
2. Synchrotron Radiation considerations

And if of interest, I have added a discussion of:

3. Cost vs. bending fields

# 1) LUMINOSITY

$$\mathcal{L} \propto \frac{\gamma}{\beta^*} I \Delta\nu \quad I \propto (f N_p) \quad \Delta\nu \propto \left( \frac{N_p}{\epsilon_{\perp}} \right)$$

where  $f$  = bunch frequency,  $N_p$  = protons per bunch,  $\epsilon_{\perp}$  = normalized rms transverse emittance,  $\beta^*$  = IP Courant-Snyder function,  $\Delta\nu$  = beam-beam tune shift, and  $I$  = beam current


Fundamental cross sections fall with  $1/\gamma^2$ , so lumiosity should rise as  $\gamma^2$ . Going from LHC at 14 TeV to 100 TeV we need:

$$\mathcal{L}_{100} \geq 1 \cdot 10^{34} \times \left( \frac{100}{14} \right)^2 = 5 \cdot 10^{35} \quad (\text{cm}^{-2}\text{s}^{-1})$$

# FCC Average Luminosities

Assuming  $I = 0.5$  amp 100 TeV  $B = 16$  T

Luminosities  $10^{35} \text{ cm}^{-2} \text{ s}^{-1}$



Averages

Phase 2  $\sim 1.0$

Phase 1  $\sim 0.3$




**phase 1:**  $\beta^* = 1.1$  m,  $\Delta Q_{\text{tot}} = 0.01$ ,  $t_{\text{ta}} = 5$  h

**phase 2:**  $\beta^* = 0.3$  m,  $\Delta Q_{\text{tot}} = 0.03$ ,  $t_{\text{ta}} = 4$  h

Well below physics ideal of  $5.0 \cdot 10^{35} \text{ cm}^{-2} \text{ s}^{-1}$

# Beyond FCC Phase 2

- Average luminosity is restricted by need for 4-5 hour turn-around time
- But, as proposed, injector train idle for 1/2 the time
- Ave luminosity could be increased by a full circumference, fixed field ( $\approx 1T$ ) permanent magnet accumulator ring
- Filling ring is done  $\approx 100\%$  of time
- Transfer from accumulator to main ring in one turn
- Lost time only needed for ramp up and down ( $2 \times 20$  min.  $\approx 1$  hour)
- Space for accumulator should be set aside at start



With a reduction of  $\beta^*$ , Luminosity  $\rightarrow 5 \cdot 10^{35} \text{cm}^{-2}\text{s}^{-1}$

# Interactions/ Bunch Crossing

$$\mathcal{L} \propto \frac{\gamma I}{\beta^*} \Delta\nu \quad I \propto (f N_p) \quad \Delta\nu \propto \left( \frac{N_p}{\epsilon_{\perp}} \right)$$



With the luminosity goal of  $5 \cdot 10^{35} \text{ cm}^{-2}\text{s}^{-1}$  and an LHC like bunch spacing ( $\approx 25\text{ns}$ ), the event pile up is excessive ( $\approx 1700$ ). Only by increasing  $f$  by 5 (bunch spacing 5 ns) and decreasing  $N_p$  by 1/5 can the pile up be constrained with a fixed current  $I$ .

To keep the total luminosity at the goal, we must, and now can, reduce emittance  $\epsilon_{\perp} 1.1 \mu\text{m} \rightarrow 0.25 \mu\text{m}$ .

Needs active cooling (as in RHIC) e.g. in accumulator


## 2) SYNCHROTRON RADIATION

- Cryogenic cooling of the dump requires its temperature to be  $\geq$  heating 50 K
- CERN FCC design nicely traps the radiation outside the beam screen
- But having the whole beam screen at 50 K increases the resistive impedance of the copper coating






# Ideal Screen Design





Unfortunately I do not see how to vertically restrain the screen in a quench

# Open Mid-Plane Dipoles



I doubt this is necessary

# Synchrotron gen. of e Cloud



- Central density in quadrupoles 2-3 orders of magnitude times that in Dipoles
- Requires Secondary Emission Coefficient  $< 1.2$  : **hard**

# One Proposed solution

## Cryogenic Beam Vacuum System Conception

Present and future surface modifications for the mitigation of electron clouds in cryogenic beam vacuum systems



[R. Valizadeh (STFC)]

The technique can easily be applied to existing vacuum surfaces where the improvement has to be done *in-situ*.

The blackening process can be carried out in air at atmospheric pressure.

The process is also readily scalable to large areas.

The surface is highly reproducible and offers a very stable surface chemistry which can be influenced during the process.



# Another Possible solution

Add a dipole field to the quadrupoles

- Dipole field must only be enough to move zero field location out of the beam tube:  
i.e. A combined function magnet
- If quad coils inside one or more dipole layer, tuning not a problem

# CONCLUSIONS

- We have useful expertise
- And many ideas that may be relevant
- Given DoE support, we would like to collaborate

I have included a discussion of Cost vs. Collider Bending Fields, but am not sure if this is of interest when the development of high field technology is a significant motivation

# 3) Cost vs. Collider Bending Fields

R. B. Palmer, Brett Parker (BNL),  
Bill Foster (FNAL/Congress)

BNL Tech Note 317B/25B, 5/1/84 (1984).

Preliminary results presented to R&D Panel

White Paper submitted to R&D Panel

Abstract submitted to IPAC15


# Method

- For different bending fields and different fractions of NbTi, Nb<sub>3</sub>Sn, & HTS conductors:
  - Calculate Yoke cross section for minimal saturation
  - Find collar dimensions to hold coil forces
  - Use CERN estimated sc costs and SSC data for support, yoke, cryogenic, and tunnel costs
- Find fractions of conductors to minimize magnet costs
- Determine total magnet and tunnel costs vs. field


At low fields tunnel and other 'linear' costs dominate. At high fields super-conductor and other magnet costs dominate. Between these is a minimum



# Costs vs. Bending fields



# Sensitivity to Assumptions



# CONCLUSION

- This analysis suggests that 20 T is significantly more expensive than  $\leq 16$  T
- This conclusion does not seem sensitive to the assumptions
- But the result may not be relevant if the development of very high field technology is a significant motivation